



STREET NAME	PAVEMENT CONDITION RATING (PCR)	Previous Priority Rating	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033
Cross Street	17.5	2	Mill, shim + 2" overlay							Contracted preservation, hot crack-fill		
Third Street	24.1	2	Mill, shim + 2" overlay							Contracted preservation, hot crack-fill		
Pease Lane	29.95	1			FDR, cross culvert, stabilization fabric + 2.5" depth 19 mm asphalt binder	Overlay 1.5" depth 12.5 mm asphalt wearing course						Contracted preservation, hot crack-fill
Second Street	35.3	2	Mill, shim + 2" overlay road, pave sidewalk 3" depth							Contracted preservation, hot crack-fill		
Hall Street	38.1	1	DPW, excavate existing failed asphalt and fine grade, contractor pave 2.5" binder + 1.5" top									
South Street	42.15	2	DPW Trench Patch Following RWSD Work	Mill, shim + top 2" depth overlay 12.5 mm asphalt Curb to Curb						Contracted preservation, hot crack-fill		
Highland Avenue	42.9	1		FDR + 2.5" Depth 19 mm asphalt binder	Overlay 1.5" depth 12.5 mm asphalt wearing course							
Church Street	46.5	3	Contracted preservation, hot crack fill			FDR + 2.5" depth asphalt binder	Overlay 1.5"					Contracted preservation, hot crack-fill
Old Mill Lane	47.35	5									Box Culvert and Paving	FDR + 2.5" Binder
Berwick Street	48.6	2	DPW, excavate existing failed asphalt and fine grade, contractor pave 2.5" binder + 1.5" top									
Front Street	49.1	2	1.5" top Trench Patch Following RWSD Work	Mill top 2" and Overlay Curb to Curb (Street Limits Int. Main St. to South St.)						Contracted preservation, hot crack-fill		



STREET NAME	PAVEMENT CONDITION RATING (PCR)	Previous Priority Rating	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033
General Sullivan Way	51.1	2	Various patch segments, DPW to prepare grade, contractor pave 2.5" binder + 1.5" top		FDR + 2.5" depth 19 mm asphalt binder	Overlay 1.5" depth 12.5 mm asphalt wearing course						
Howe Road	51.8	2	Contracted preservation, hot crack fill			1" Paver Shim + 2" Overlay						
Pleasant Street	53.1	3	Contracted preservation, hot crack fill				1.5" depth overlay 12.5 mm asphalt wearing course					
Pine Street	53.3	1		DPW, patching		FDR + 2.5" depth 19mm asphalt binder	Overlay 1.5" depth 12.5 mm asphalt wearing course					
Kelwyn Drive	54.4	1		FDR + 2.5" Depth of 19 mm Binder Est.		Overlay 1.5" Depth 12.5 mm asphalt wearing course						
Silver Street Extension	54.55	2	FDR + 2.5" Binder + 1.5" Top									
Toll Road	55.7	3				FDR + 2.5" Binder	Overlay 1.5"					
Doherty Lane	56.8	3	DPW, patching .						FDR +2.5" Binder	Overlay 1.5"		
Ross Road	59.9	3				FDR + 2.5" Binder	Overlay 1.5"					
Cricket Lane	60.5	3	Contracted preservation, hot crack-fill					2" Overlay				
Turgeon Way	61.6	3	DPW, patching .				FDR + 2.5" Binder	Overlay 1.5"				
Prospect Street	62.25	4			FDR, drainage plan + 2.5" depth 19 mm asphalt binder	Overlay 1.5" depth 12.5 mm asphalt wearing course						
Lower Mill Road (RWSD ROW)	63	1		Mill top 2" and pave from Front Street to toe of slope								
Woodland Drive	64.2	2		DPW, patching .				FDR + 2.5" Binder	Overlay 1.5"			
Mechanic Street	70.15	5	Contracted preservation, hot crack-fill									



STREET NAME	PAVEMENT CONDITION RATING (PCR)	Previous Priority Rating	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033
Cottage Lane	71.45	5		DPW, patching Est. 1.4K, Contracted preservation, hot crack-fill				FDR + 2.5" Binder	Overlay 1.5"			
Silver Lane	72.3	4	Contracted preservation, hot crack-fill					FDR + 2.5" Binder	Overlay 1.5"			
Old Indigo Hill Road	74.3	5	Contracted preservation, hot crack-fill			2" Overlay						
Willy Street	75.3	5	Contracted preservation, hot crack-fill									Overlay 1.5"
Oak Street	77.85	N/A	Various patch segments, DPW to prep and pave.	Contracted preservation, hot crack-fill								
Settlement Circle	78.8	5	DPW, patching							Overlay 1.5"		
Spruce Street	79.15	5	Contracted preservation, hot crack-fill									
Heritage Drive	79.2	5	Contracted preservation, hot crack-fill									
Locust Street	80.4	5						Segment from Foundry to Pine FDR + 2.5" Binder		Overlay 1.5"		
Stockdale Circle	80.6	2					Mill + 2.5" depth 12.5 mm asphalt overlay					
Moses Carr Road	81.2	5	Contracted preservation, hot crack-fill									
Greenview Drive	84.05	5	Contracted preservation, hot crack-fill				Contracted preservation, asphalt rubber stress absorbing chip seal (SAM)			Overlay 1.5"		
Foundry Street	89.5	5	Contracted preservation, hot crack-fill				Contracted preservation, asphalt rubber stress absorbing chip seal (SAM)					



STREET NAME	PAVEMENT CONDITION RATING (PCR)	Previous Priority Rating	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033
Gilman Street	89.5	N/A	Contracted preservation, hot crack-fill									
Pinch Hill Road	89.5	5	Contracted preservation, asphalt rubber stress absorbing chip seal (SAM)									Contracted preservation, microsurface chip seal
Pinecrest Lane	90.25	4	Contracted preservation, hot crack-fill									
Wentworth Street	90.5	5	Contracted preservation, hot crack-fill									
Washington Street	91.05	5						Contracted preservation, hot crack-fill				
Franklin Street	92.05	5						Contracted preservation, hot crack-fill				
Baer Road	92.5	5	Contracted preservation, asphalt rubber stress absorbing chip seal (SAM)									Contracted preservation, microsurface chip seal
Sligo Road	92.5	5		Contracted preservation, asphalt rubber stress absorbing chip seal (SAM)								Contracted preservation, microsurface chip seal
Clement Road	92.5	5	Contracted preservation, hot crack-fill									
Water Street	94.5	5	Contracted preservation, hot crack-fill									
Beccaris Drive	95.5	5								Contracted preservation, hot crack-fill		
Fourth Street	96	5						Contracted preservation, hot crack-fill				



STREET NAME	PAVEMENT CONDITION RATING (PCR)	Previous Priority Rating	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033
Railroad Avenue	96	5						Contracted preservation, hot crack-fill				
River Road	96.5	5						Contracted preservation, hot crack-fill				
Woods Run	96.5	5						Contracted preservation, hot crack-fill				
Willey Street Extension	98.1	5								Contracted preservation, hot crack-fill		
Stevens Court	99	5								Contracted preservation, hot crack-fill		
Jessie Doe Road	100	5								Contracted preservation, hot crack-fill		
Scarlett Circle	100	5								Contracted preservation, hot crack-fill		
Partridge Lane	100	5								Contracted preservation, hot crack-fill		
Watson Lane	100	5								Contracted preservation, hot crack-fill		